

ADDENDUM #4

to Bid Documents For:

Nursery Blvd New Box Culvert Construction

Project #2019-06

Baker County, Florida

August 13, 2019

This addendum shall be considered part of the plans, specifications and contract documents and is issued to change, add or delete from or otherwise explain the documents further. This addendum shall have precedence over the original documents and shall govern.

I. Responses to questions by contractors

Question: There are differences in the lengths of the box culvert wingwalls between the plan view and the box culvert details. The plan view (sheet 511) shows the wingwall lengths to 34 ft for the right begin, 22 ft for the right end, 19 ft for the left begin and 33 ft for the left end, while the Box Culvert Detail (sheet CBC-2) calls out for each one to 10 ft long.

The longer walls will increase the cubic yards of concrete and the pound of steel required for the project above what is called for in the Box Culvert Detail sheets. Since the Box Culvert with Wingwalls is a Lump Sum item, which option should we bid with?

Response: Tarbox plan Sheet 557 needs to be used for the required dimensions of wingwalls (not sheet cbc-2). Bidder shall include all costs associated with achieving required dimensions of wingwalls as shown on sheet 557 in the lump sum pay item for the box culvert.