

EXISTING MAILBOXES TO BE RELOCATED

ID	MAILBOX ADDRESS	STATION	CURRENT OFFSET & SIDE	MIN. OFFSET TO FACE OF MAILBOX (FROM CL)	MIN. OFFSET TO FACE OF MAILBOX (FROM ETW)
MB-X01	9324 BRENT LANE	17+70	34 (L)	16' (L)	4'
MB-X02	9340 LOADHOLTZ	19+31	7 (R)	16' (R)	4'
MB-X03	9408 LOADHOLTZ	19+32	7 (R)	16' (R)	4'
MB-X04	5517 WILLIS HODGES	22+10	9 (R)	16' (R)	4'
MB-X05	5518 WILLIS HODGES	22+11	9 (R)	16' (R)	4'

EXISTING AND PROPOSED SIGNS

ID	SIGN DESCRIPTION	STATION	MIN. OFFSET TO EDGE OF SIGN FROM NEW EDGE OF PAVEMENT	NOTES
STOP-X01	STOP-X01	5+64.65	6'	SIGN TO REMAIN
STOP-X02	STOP-X02	7+01.78	6'	SIGN TO REMAIN
STOP-X03	STOP-X03	7+72.41	6'	SIGN TO REMAIN
STOP-X04	STOP-X04	9+82.24	6'	SIGN TO REMAIN
STOP-P01	STOP-P01	8+90.93	6'	NEW SIGN
STOP-P02	STOP-P02	10+09.07	6'	NEW SIGN
STOP-P03	STOP-P03	15+14.88	6'	NEW SIGN

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS	PAY ITEM NUMBER	ITEM DESCRIPTION	QTY	UNITS
0110 1 1	CLEARING AND GRUBBING	0.19	AC	0530 3 4	RIPRAP, RUBBLE, F&I DITCH LINING	0	TN
0120 1	REGULAR EXCAVATION	326	CY	0570 1 1	PERFORMANCE TURF - SEED	433	SY
0120 2 2	BORROW EXCAVATION - TRUCK MEASURE	52	CY	0570 1 2	PERFORMANCE TURF - SOD	867	SY
0120 4	REMOVE AND REPLACE UNSUITABLES	1	CY	0700 1 11	SGL. POST SIGN, F&I GND. MNT. < 12 SF	3	EA
0120 6	EMBANKMENT	364	CY	0706 1	RETRO-REFL. RPMS	50	EA
0160 4	TYPE B STABILIZATION	1,733	SY	0710 11101	PAINTED PVMT. MRKS. STD. WHT. SLD. 6'	4,792	LF
0162 1 11	PREPARED SOIL LAYER (2")	1,300	SY	0710 11102	PAINTED PVMT. MRKS. STD. WHT. SLD. 8'	132	LF
0285702	DBG 2	17	SY	0710 11125	PAINTED PVMT. MRKS. STD. WHT. SLD. 24'	96	LF
0285706	DBG 6	1,902	SY	0710 11201	PAINTED PVMT. MRKS. STD. YEL. SLD. 6'	4,110	LF
0327	MILLING	1	LS				
0334 1 53	SP 9.5, TRAFFIC C, PG76-22	2.5	TN				
0334 1 53	SP 12.5, TRAFFIC C, PG76-22	201.0	TN				
0400 1 2	CONC. CLASS I, ENDWALLS	0	CY				
0425 5	ADJUST SANITARY SEWER MANHOLE	1	EA				
0520 2105	CONCRETE CURB 6' X 18'	38	LF				

BASE BID

- THE MATERIAL QUANTITIES SHOWN ON THIS PLAN SHEET ARE FOR THE **BASE BID** OPTION.
- THE MATERIAL QUANTITIES SHOWN ON THESE PLANS ARE PROBABLE QUANTITIES AND IT IS HEREBY NOTED THAT ACTUAL QUANTITIES MAY VARY.
- FOR UNIT COST ITEMS, WHEN ACTUAL QUANTITIES DIFFER FROM PROBABLE QUANTITIES SHOWN ON THESE PLANS, ACTUAL QUANTITIES WILL BE USED TO DETERMINE COMPENSATION.
- CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING QUANTITIES FOR LUMP SUM BID ITEMS.
- NOT ALL CONSTRUCTION COSTS CAN BE DETERMINED FROM THE QUANTITIES REPORTED IN THESE PLANS. THE QUANTITIES REPORTED IN THESE PLANS ARE TO PROVIDE SOME OF THE INFORMATION THE CONTRACTOR WILL NEED TO PREPARE THEIR BID.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO INSURE THAT THEIR BID UNIT PRICES AND BID ITEM PRICES COVER ALL MATERIALS, EQUIPMENT, LABOR, OVERHEAD AND CONTRACTOR PROFIT SO THAT THE CONTRACTOR CAN COMPLETE THE IMPROVEMENTS SHOWN ON THESE PLANS IN ACCORDANCE WITH APPLICABLE STANDARDS.

DRAINAGE STRUCTURE TABLE

ID	TYPE	TOP ELEV	INVERTS	NORTHING	EASTING
DS-050	TYPE D DBI TYP. P, ALT. B FDOT 425-052	121.50	118.75 (W) 115.80 (E)	467900.80	2717314.80
DS-060	TYPE D DBI TYP. P, ALT. B FDOT 425-052	124.00	115.90 (W) 122.00 (E) 116.00 (E)	467898.36	2717384.90
DS-061	WINGED EW FDOT 430-040		122.10 (W)	467898.42	2717387.88
DS-070	MANHOLE-TYPE 8 FDOT 425-001	124.75	116.30 (W) 116.40 (E)	467893.19	2717615.64
DS-080	MANHOLE TYPE 8 ALT. B BOTTOM FDOT 425-001	124.35	116.70 (W) 116.80 (S) 120.30 (N)	467899.60	2717910.80
DS-081	TYPE C DBI W/ CONC. APRON FDOT 425-052	124.00	120.50 (S)	467924.73	2717910.00
DS-090	MANHOLE-TYPE 8 FDOT 425-001	124.63	116.90 (N) 117.00 (E)	467881.45	2717911.31
DS-095	MANHOLE-TYPE 8 FDOT 425-001	124.80	118.50 (W) 118.60 (S)	467888.03	2718190.64
DS-099	CONCRETE COLLAR FDOT 430-001		118.75 (N) 118.75 (S)	467877.94	2718190.69

PIPE TABLE

ID	DIA (IN)	INSIDE WIDTH (IN)	INSIDE HEIGHT (IN)	LENGTH (FT)	US INV.	DS INV.	SLOPE (PERCENT)
P-060	24	24	24	70	115.90	115.80	0.14%
P-061	15	15	15	3	122.10	122.00	3.36%
P-070	24	24	24	231	116.30	116.00	0.13%
P-080	24	24	24	295	116.70	116.40	0.10%
P-081	18	18	18	25	120.50	120.30	0.80%
P-090	24	24	24	18	116.90	116.80	0.55%
P-095	24	24	24	279	118.50	117.00	0.54%
P-099	24	24	24	10	118.75	118.60	1.49%

REVISIONS

DATE	DESCRIPTION	DATE	DESCRIPTION
06/27/2023	BID ADDENDUM #2		



TROY W. TARBOX, P.E.
FLA. P.E. LICENSE NO. 50661
TARBOX CONSULTING AND DESIGN, INC.
3716 RUBIN ROAD
JACKSONVILLE, FL 32257
CERTIFICATE OF AUTHORIZATION 23132



**WILLIS HODGES ROAD
IMPROVEMENT PROJECT**

**CONSTRUCTION QUANTITIES
BASE BID**

DRAWING NO.

150