

## BID FORM

**County Road 127 North - Phase 2 : Road Segment 2 (from SR-2 to Mocassin Creek Road)**  
**Alternate Bid 1 - Overlay and Widening plus Box Culvert Extension**

Date: \_\_\_\_\_

Bidding Company: \_\_\_\_\_

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
1	101	<b>Mobilization</b>	1	LS			
2	102	<b>Maintenance of Traffic</b>	1	LS			
3	104	<b>Erosion and Sediment Control</b>	1	LS			
4	110	<b>Demolition</b>					
		Removal of Cross Drain Headwalls	-	EA			
		Removal of CBC Headwalls/Wingwalls	2	EA			
		Removal of Existing Guardrail	831	LF			
		Removal of Single Post Sign	4	EA			
		Relocate Mailbox	6	EA			
		Sawcuts	15,578	LF			
5	120 & 160	<b>Earthwork</b>					
		Excavation - Regular	649	CY			
		Type B Stabilization	435	SY			
6	120	<b>Shoulder Rework</b>	649	CY			
7	285	<b>Base Material</b>					
		Widening (OBG4)	3,458	SY			
		Base Material for SideRoads (OBG4)	435	SY			
		New Driveway Turnouts (OBG 2)	87	SY			
8	327	<b>Milling Existing Asphalt</b>					
		1" Milling Depth	10	SY			
		0.5" Milling for Superelevation Correction	2,675	SY			
9	334	<b>Asphaltic Pavement</b>					
		Asphalt Leveling Course (75 lbs/SY)	584	TON			
		Asphaltic Pavement (SP12.5 PG76-22)	1,657	TON			
10	400	<b>Concrete Box Culvert</b>					
		Class IV, 5.5 KSI Concrete	48	CY			
		Grade 60 Reinforcing Steel	7,777	LBS			
11	430	<b>Storm - Pipe Culverts</b>					
		24" Round	-	LF			
12	430	<b>Storm - End Treatments</b>					
		Conc. Collar 24" (430.001)	-	EA			
		FDOT HEADWALL (430-030) DBL. 24"	-	LF			

## BID FORM

**County Road 127 North - Phase 2 : Road Segment 2 (from SR-2 to Mocassin Creek Road)**  
**Alternate Bid 1 - Overlay and Widening plus Box Culvert Extension**

Date: \_\_\_\_\_

Bidding Company: \_\_\_\_\_

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
<b>13</b>	<b>536</b>	<b>Guardrail</b>					
		Guardrail - TL-3 (High Speed)	572	LF			
		Special Steel Posts for Concrete Mount	4	EA			
		End Treatment - Approach Terminal	2	EA			
		End Treatment - Trailing Anchorage	2	EA			
<b>14</b>	<b>570</b>	<b>Performance Turf</b>					
		Performance Turf (Seed)	2,832	SY			
		Performance Turf (Sod)	6,767	SY			
<b>15</b>	<b>700</b>	<b>Traffic Signage</b>					
		F&I Single Post Sign < 12SF	15	EA			
		F&I Multi-Post Sign, Ground Mount, > 12SF	3	EA			
<b>16</b>	<b>705</b>	<b>Object Markers</b>					
		Object Markers, Type 2	4	EA			
<b>17</b>	<b>706</b>	<b>Raised Pavement Markers</b>					
		Raised Pavement Markers	348	EA			
<b>18</b>	<b>710 &amp; 711</b>	<b>Traffic Markings</b>					
		White Solid 6" Paint	31,288	LF			
		White Solid 24" Paint	72	LF			
		Yellow 6" Skip (10'/30') Paint	14,082	LF			
		Yellow 6" Solid Paint	14,014	LF			
<b>19</b>	<b>000</b>	<b>Construction Bond</b>	1	LS			
<b>TOTAL BID AMOUNT =</b>							