

GENERAL PROVISIONS
PAVING/RESURFACING OF
REID STAFFORD ROAD – PHASE II (SECTION A)
Baker County Project No. **2021-01**

separate contract(s) based on the same Bid Item Unit Prices specified in the Bid, providing both parties agree.

R. MEASUREMENT AND PAYMENT

Measurement of and payment for bid items shall be in accordance with FDOT Specifications unless otherwise noted in the Bid Documents, or, as noted in this section of the Bid Manual. In general, payment shall be made following County approval of pay applications and in accordance with County payment policies.

Bid Item	FDOT Pay Item	Measurement and Payment for Baker County Project
1	101-1	Mobilization <u>Measurement:</u> Per FDOT Specifications, Section 101. <u>Payment:</u> Incremental payments, not totaling more than the lump sum bid amount, shall be made based on the percent of Contract Time elapsed.
2	102-1	Maintenance of Traffic <u>Measurement:</u> Per FDOT Specifications Section 102. <u>Payment:</u> Incremental payments, not totaling more than the lump sum bid amount, shall be made based on the percent of Contract Time elapsed.
3	104-10	Erosion and Sediment Control: <u>Measurement:</u> Per FDOT Specifications, Section 104. <u>Payment:</u> Incremental payments, not totaling more than the lump sum bid amount, shall be made based on the percent of Contract Time elapsed.
4	110-1-1	Clearing and Grubbing <u>Measurement:</u> Per FDOT Specifications, Section 110. <i>Contractor shall be aware that the County has performed a significant portion of the clearing and grubbing required for this project. The Contractor shall thoroughly inspect the project site, prior to construction, to determine the extent of clearing and grubbing activities that have</i>

GENERAL PROVISIONS
PAVING/RESURFACING OF
REID STAFFORD ROAD – PHASE II (SECTION A)
Baker County Project No. **2021-01**

not yet been performed. These activities will be the responsibility of the Contractor.

Payment: Incremental payments, not totaling more than the lump sum bid amount, shall be made based on the percent of work completed.

- | | | |
|---|---------|---|
| 5 | N/A | <p>Mailbox, Relocate</p> <p><u>Measurement:</u> Per mailbox assembly, including post and box, acceptably relocated.</p> <p><u>Payment:</u> Price and payment will be full compensation for all work required, including supports.</p> |
| 6 | 120-1 | <p>Regular Excavation (Contingency)</p> <p><u>Measurement:</u> Per FDOT Specifications, Section 120.</p> <p><u>Payment:</u> Incremental payments shall be made based on the volume, in cubic yards, excavated during the pay application period.</p> |
| 7 | 120-6 | <p>Embankment (Contingency)</p> <p><u>Measurement:</u> Per FDOT Specifications, Section 120.</p> <p><u>Payment:</u> Incremental payments shall be made based on the volume, in cubic yards, placed and accepted during the pay application period.</p> |
| 8 | 160-4 | <p>Type B Stabilization (12")</p> <p><u>Measurement:</u> Per FDOT Specifications, Section 160.</p> <p><u>Payment:</u> Incremental payments shall be made based on the area, in square yards, completed and accepted during the pay application period.</p> |
| 9 | 285-704 | <p>Optional Base Course</p> <p><u>Measurement:</u> Per FDOT Specifications, Section 285.</p> <p><u>Payment:</u> Incremental payments shall be made based on the area in square yards, as shown on the Plans, constructed and accepted</p> |

GENERAL PROVISIONS

PAVING/RESURFACING OF
REID STAFFORD ROAD – PHASE II (SECTION A)
Baker County Project No. **2021-01**

during the pay application period. There shall be no payment adjustments based on average thickness.

10 334-1 Asphaltic Concrete SP (1.5")

Measurement: Per FDOT Specifications, Section 334.

Payment: Incremental payments shall be made based on the weight in tons (2,000 lbs per ton) of asphaltic concrete pavement constructed and accepted during the pay application period.

11 400-1 Class I Concrete, Endwalls

Measurement: Per FDOT Specifications, Section 400.

Payment: Incremental payments shall be made based on the volume, in cubic yards, as shown on the Plans, constructed and accepted during the pay application period.

12-18 430-17A Pipe Culverts, Side Drains & Cross Drains

Measurement: Per FDOT Specifications, Section 430.

Payment: Incremental payments shall be made based on the length of each type of pipe, as shown on the Plans, constructed and accepted during the pay application period.

19-23 430-98A Mitered End Sections

Measurement: Per FDOT Specifications, Sections 430.

Payment: Incremental payments shall be made based on the number of inlets constructed, as shown on the Plans, and accepted during the pay application period.

**24-25 530-3 &
530-74 Rubble RipRap Ditch Lining & Bedding Stone**

Measurement: Per FDOT Specifications, Sections 530.

Payment: Incremental payments shall be made based on the weight, in tons, as shown on the Plans, constructed and accepted during the pay application period.

GENERAL PROVISIONS
PAVING/RESURFACING OF
REID STAFFORD ROAD – PHASE II (SECTION A)
Baker County Project No. **2021-01**

26-27 570-1

Performance Turf

Measurement: Per FDOT Specifications, Sections 570.

Payment: Incremental payments shall be made based on the the area in square yards, as shown on the Plans, constructed and accepted during the pay application period.

28-29 700-1

Single Post Signs

Measurement: Per FDOT Specifications, Section 700.

Payment: Incremental payments shall be made based on the number of sign assemblies Furnished and Installed, Removed or Relocated, as shown on the Plans, and accepted during the pay application period.

30 700-12

Sign Beacon

Measurement: Per FDOT Specifications, Section 700.

Payment: Incremental payments shall be made based on the number of sign beacon assemblies Furnished and Installed, as shown on the Plans, and accepted during the pay application period.

31 705-10

Object Markers

Measurement: Per FDOT Specifications, Section 705.

Payment: Incremental payments shall be made based on the number of object markers Furnished and Installed, as shown on the Plans or in the Standard Plans, and accepted during the pay application period.

32 706-3

Raised Pavement Markers (RPMs)

Measurement: Per FDOT Specifications, Section 706.

Payment: Incremental payments shall be made based on the number of RPMs Furnished and Installed, as shown on the Plans, and accepted during the pay application period.

33-38 710-11

Traffic Markings

Measurement: Per FDOT Specifications, Section 710.

GENERAL PROVISIONS

PAVING/RESURFACING OF REID STAFFORD ROAD – PHASE II (SECTION A) Baker County Project No. 2021-01

Payment: Incremental payments shall be made based on the lengths of lines and number of messages, symbols and arrows, as shown on the Plans and as constructed during the pay application period.

39 N/A

As-Built Drawings

General:

1) Submit Two (2) signed and sealed sets of prints and one digital copy (MicroStation format; **Please do not use Reference files**) with the design information (elevations, pipe lengths, stationing, etc.) lined through ~~(28-48)~~ and the as-built information placed adjacent to it.

NOTE: The firm or licensed surveyor shall use the original paving sheet(s) specifically for as-built information. The drawing(s) are to be on 11" X 17" sheet(s) and contain the following in addition to the as-built information:

- Project name as it appears on the plans
 - Project/Development number
 - Street names
 - Design information for all as-built information provided lined through
 - North arrow and scale
 - Show and label all survey-lines used for locations
- 2) The words "AS-BUILT" in at least one-inch high letters
 - 3) Materials certification statement signed by the contractor
 - 4) Signed engineer's certification statement
 - 5) Information pertaining to benchmark(s) (location, elevation, and reference type)
 - 6) Show **STATE PLANE COORDINATE (NAD. 83)**

Paving

Stations, offsets, and elevations on:

- Center-line or profile grade line
- Edge of Pavement
- A minimum of every 100 feet and at the following changes in vertical and horizontal alignment: PVC, PC and PVT

Payment: Lump sum payment shall be made upon completion and acceptance of all As-Built drawings.