

## Bid Tabulation Form - Base Bid

County Road 127 North - Phase 2  
Road Segment 1

Bid By: \_\_\_\_\_

Baker County, Florida

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
1	101	Mobilization	4.546	GM			
2	102	Maintenance of Traffic	4.546	GM			
3	104	Erosion and Sediment Control	4.546	GM			
4	110	Demolition					
		Clearing and Grubbing - Light	1.29	AC			
		Removal of Cross Drain Headwalls	4	EA			
		Removal of CBC Headwalls/Wingwalls	2	EA			
		Removal of Existing Guardrail	344	LF			
		Removal of Signs	27	EA			
		Removal of Mailboxes	33	EA			
		Sawcuts	82	LF			
5	120	Shoulder Rework	1,958	CY			
6	120 & 160	Earthwork					
		Excavation - Regular	2,842	CY			
		Embankment	5,195	CY			
		Borrow - Structural Fill	1,440	CY			
		Borrow - Nonstructural Fill	913	CY			
		Type B Stabilization	1,356	SY			
7	285	Base Material					
		Widening (OBG 6)	11,094	SY			
		Full Depth Reclamation (OBG 1)	54,582	SY			
		New Side Roads (OBG 6)	1,356	SY			
		New Driveway Turnouts (OBG 2)	825	SY			
8	327	Milling Existing Asphalt					
		Sideroad Milling	192	SY			
		Butt Joint Milling	410	SY			
9	332	Full-Depth Reclamation					
		STA 291+78 to 520+40	52,075	SY			
		STA 520+80 to 531+81	2,508	SY			
10	334	Asphaltic Pavement					
		Resurface Side Roads: SP12.5, C, PG76-22	15.8	TON			
		Resurface Dvwy Turnouts: SP, C, PG76-22	3.3	TON			
		Miscellaneous Asphalt: SP12.5, C, PG76-22	76.6	TON			
		New Side Roads: SP12.5, C, PG76-22	141.2	TON			
		New Dvwy Turnouts: SP12.5, C, PG76-22	68.1	TON			
11	400	Concrete Box Culvert - Concrete					
		Class IV, 5.5 KSI Concrete	94.53	CY			
		(Includes Grade 60 Reinforcing Steel)					

## Bid Tabulation Form - Base Bid

County Road 127 North - Phase 2

Road Segment 1

Baker County, Florida

Bid By: \_\_\_\_\_

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
12	430	<b>Storm Drainage - Pipe</b>					
		24" Round	110	LF			
		36" Round	101	LF			
13	430	<b>Storm Drainage - End Sections</b>					
		Conc. Collar 24" (430.001)	8	LF			
		Conc. Collar 36" (430.001)	16	LF			
		FDOT MES (430-021) SGL. 24" (4:1)	4	LF			
		FDOT MES (430-021) DBL. 24" (4:1)	2	LF			
		FDOT MES (430-021) DBL. 36" (4:1)	2	LF			
		FDOT MES (430-021) TPL. 36" (4:1)	2	LF			
		FDOT HEADWALL (430-030) DBL. 24"	2	LF			
		FDOT HEADWALL (430-030) SGL. 36"	2	LF			
14	536	<b>Guardrail</b>					
		Guardrail - TL-3 (High Speed)	338	LF			
		Special Steel Posts for Concrete Mount	8	EA			
		End Treatment - Approach Terminal	4	EA			
15	570	<b>Performance Turf</b>					
		Performance Turf (Seed)	55,914	SY			
		Performance Turf (Sod)	23,963	SY			
16	700	<b>Signage</b>					
		F&I Single Sign Post < 12SF	38	EA			
		Mailboxes	33	EA			
17	705	<b>Object Markers</b>					
		Object Markers, Type 2	22	EA			
18	706	<b>Raised Pavement Markers</b>					
		Raised Pavement Markers	1,007	EA			
19	710 & 711	<b>Traffic Markings</b>					
		White Solid 6" Paint	96,594	LF			
		White Solid 24" Paint	137	LF			
		Yellow 6" Skip (10'/30') Paint	42,666	LF			
		Yellow 6" Solid Paint	38,344	LF			
		White 24" Thermoplastic	137	LF			
		White Message Thermoplastic	2	EA			
20	000	<b>Construction Bond</b>	1	LS			
Bidder has checked all calculations for accuracy prior to bid submittal.					<b>TOTAL BID =</b>		