

## Bid Tabulation - Alternate Bid

County Road 127 North - Phase 2  
Road Segment 2  
Baker County, Florida

Bid By:

(company name)

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
1	101	Mobilization	1.473	GM			
2	102	Maintenance of Traffic	1.473	GM			
3	104	Erosion and Sediment Control	1.473	GM			
4	110	Demolition					
		Clearing and Grubbing - Light	1.29	AC			
		Removal of Cross Drain Headwalls	4	EA			
		Removal of CBC Headwalls/Wingwalls	2	EA			
		Removal of Existing Guardrail	831	LF			
		Removal of Signs	4	EA			
		Removal of Mailboxes	6	EA			
		Sawcuts	18	LF			
5	120	Shoulder Rework	2,543	CY			
6	120 & 160	Earthwork					
		Excavation - Regular	914	CY			
		Embankment	3,488	CY			
		Borrow - Structural Fill	1,775	CY			
		Borrow - Nonstructural Fill	799	CY			
		Type B Stabilization	435	SY			
7	285	Base Material					
		Widening (OBG 6)	3,602	SY			
		New Side Roads (OBG 6)	435	SY			
		New Driveway Turnouts (OBG 2)	219	SY			
8	327	Milling Existing Asphalt					
		Mainline Milling	-	SY			
		Sideroad Milling	-	SY			
		Butt Joint Milling	90	SY			
9	332	Full-Depth Reclamation					
10	334	Asphaltic Pavement					
		Leveling Course (75 lbs/SY)	583.5	TON			
		Resurface Lanes: SP, C, PG76-22	1,283.7	TON			
		Miscellaneous Asphalt: SP12.5, C, PG76-22	69.9	TON			
		New Side Roads: SP12.5, C, PG76-22	45.9	TON			
		New Dvwy Turnouts: SP12.5, C, PG76-22	18.1	TON			
11	400	Concrete Box Culvert - Concrete					
		Class IV, 5.5 KSI Concrete	48.16	CY			
		(Includes Grade 60 Reinforcing Steel)					

## Bid Tabulation - Alternate Bid

County Road 127 North - Phase 2  
Road Segment 2  
Baker County, Florida

Bid By:

(company name)

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
12	430	<b>Storm Drainage - Pipe</b>					
		24" Round	24	LF			
		36" Round	-	LF			
13	430	<b>Storm Drainage - End Sections</b>					
		Conc. Collar 24" (430.001)	6	LF			
		FDOT HEADWALL (430-030) DBL. 24"	4	LF			
14	536	<b>Guardrail</b>					
		Guardrail - TL-3 (High Speed)	350	LF			
		Special Steel Posts for Concrete Mount	4	EA			
		End Treatment - Approach Terminal	4	EA			
15	570	<b>Performance Turf</b>					
		Performance Turf (Seed)	18,153	SY			
		Performance Turf (Sod)	7,780	SY			
16	700	<b>Signage</b>					
		F&I Single Sign Post < 12SF	20	EA			
		Mailboxes	7	EA			
17	705	<b>Object Markers</b>					
		Object Markers, Type 2	12	EA			
18	706	<b>Raised Pavement Markers</b>					
		Raised Pavement Markers	348	EA			
19	710 & 711	<b>Traffic Markings</b>					
		White Solid 6" Paint	31,290	LF			
		White Solid 24" Paint	37	LF			
		Yellow 6" Skip (10'/30') Paint	14,082	LF			
		Yellow 6" Solid Paint	13,871	LF			
		White 24" Thermoplastic	37	LF			
		White Message Thermoplastic	2	EA			
20	000	<b>Construction Bond</b>	1	LS			
Bidder has checked all calculations for accuracy prior to bid submittal.					<b>TOTAL BID =</b>		