

Bid Tabulation - Alternate Bid

County Road 127 North - Phase 2
Road Segment 2
Baker County, Florida

Bid By:

(company name)

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
1	101	Mobilization	1	LS	\$	-	\$ -
2	102	Maintenance of Traffic	1	LS	\$	-	\$ -
3	104	Erosion and Sediment Control	1	LS	\$	-	\$ -
4	110	Demolition					\$ -
		Clearing and Grubbing - Light	1.29	AC	\$	-	
		Removal of Cross Drain Headwalls	4	EA	\$	-	
		Removal of CBC Headwalls/Wingwalls	2	EA	\$	-	
		Removal of Existing Guardrail	831	LF	\$	-	
		Removal of Signs	4	EA	\$	-	
		Removal of Mailboxes	6	EA	\$	-	
		Sawcuts	18	LF	\$	-	
5	120	Shoulder Rework	2,543	CY	\$	-	\$ -
6	120 & 160	Earthwork					\$ -
		Excavation - Regular	914	CY	\$	-	
		Embankment	3,488	CY	\$	-	
		Borrow - Structural Fill	1,775	CY	\$	-	
		Borrow - Nonstructural Fill	799	CY	\$	-	
		Type B Stabilization	435	SY	\$	-	
7	285	Base Material					\$ -
		Widening (OBG 6)	3,602	SY	\$	-	
		New Side Roads (OBG 6)	435	SY	\$	-	
		New Driveway Turnouts (OBG 2)	219	SY	\$	-	
8	327	Milling Existing Asphalt					\$ -
		Butt Joint Milling	90	SY	\$	-	
9	332	Full-Depth Reclamation					
10	334	Asphaltic Pavement					\$ -
		Leveling Course SP9.5 (75 lbs/SY)	583.5	TON	\$	-	
		Resurface Lanes: SP12.5, C, PG76-22	1,283.7	TON	\$	-	
		New Lanes: SP12.5, C, PG76-22	570.5	TON	\$	-	
		Miscellaneous Asphalt: SP12.5, C, PG76-22	69.9	TON	\$	-	
		New Side Roads: SP12.5, C, PG76-22	45.9	TON	\$	-	
		New Dvwy Turnouts: SP12.5, C, PG76-22	18.1	TON	\$	-	
11	400	Concrete Box Culvert - Concrete					\$ -
		Class IV, 5.5 KSI Concrete (Includes Grade 60 Reinforcing Steel)	48.16	CY	\$	-	

Bid Tabulation - Alternate Bid

County Road 127 North - Phase 2
Road Segment 2
Baker County, Florida

Bid By: _____

(company name)

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
12	430	Storm Drainage - Pipe					\$ -
		24" Round	24	LF		\$ -	
13	430	Storm Drainage - End Sections					\$ -
		Conc. Collar 24" (430.001)	6	EA		\$ -	
		FDOT HEADWALL (430-030) DBL. 24"	4	EA		\$ -	
14	536	Guardrail					\$ -
		Guardrail - TL-3 (High Speed)	350	LF		\$ -	
		Special Steel Posts for Concrete Mount	4	EA		\$ -	
		End Treatment - Approach Terminal	4	EA		\$ -	
15	570	Performance Turf					\$ -
		Performance Turf (Seed)	18,153	SY		\$ -	
		Performance Turf (Sod)	7,780	SY		\$ -	
16	700	Signage					\$ -
		F&I Single Sign Post < 12SF	20	EA		\$ -	
		Mailboxes	7	EA		\$ -	
17	705	Object Markers					\$ -
		Object Markers, Type 2	12	EA		\$ -	
18	706	Raised Pavement Markers					\$ -
		Raised Pavement Markers	348	EA		\$ -	
19	710 & 711	Traffic Markings					\$ -
		White Solid 6" Paint	31,290	LF		\$ -	
		White Solid 24" Paint	37	LF		\$ -	
		Yellow 6" Skip (10'/30') Paint	14,082	LF		\$ -	
		Yellow 6" Solid Paint	13,871	LF		\$ -	
		White 24" Thermoplastic	37	LF		\$ -	
		White Message Thermoplastic	2	EA		\$ -	
20	000	Construction Bond	1	LS		\$ -	\$ -
Bidder has checked all calculations for accuracy prior to bid submittal.					TOTAL BID =		\$ -