

## Bid Tabulation - Alternate Bid

County Road 127 North - Phase 2  
Road Segment 2  
Baker County, Florida

Bid By:

(company name)

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
1	101	<b>Mobilization</b>	1	LS		\$ -	\$ -
2	102	<b>Maintenance of Traffic</b>	1	LS		\$ -	\$ -
3	104	<b>Erosion and Sediment Control</b>	1	LS		\$ -	\$ -
4	110	<b>Demolition</b>					\$ -
		Clearing and Grubbing - Light	1.29	AC		\$ -	
		Removal of Cross Drain Headwalls	4	EA		\$ -	
		Removal of CBC Headwalls/Wingwalls	2	EA		\$ -	
		Removal of Existing Guardrail	831	LF		\$ -	
		Removal of Signs	4	EA		\$ -	
		Removal of Mailboxes	6	EA		\$ -	
		Sawcuts	18	LF		\$ -	
5	120	<b>Shoulder Rework</b>	2,543	CY		\$ -	\$ -
6	120 & 160	<b>Earthwork</b>					\$ -
		Excavation - Regular	914	CY		\$ -	
		Embankment	3,488	CY		\$ -	
		Borrow - Structural Fill	1,775	CY		\$ -	
		Borrow - Nonstructural Fill	799	CY		\$ -	
		Type B Stabilization	435	SY		\$ -	
7	285	<b>Base Material</b>					\$ -
		Widening (OBG 6)	3,602	SY		\$ -	
		New Side Roads (OBG 6)	435	SY		\$ -	
		New Driveway Turnouts (OBG 2)	98	SY		\$ -	
8	327	<b>Milling Existing Asphalt</b>					\$ -
		Butt Joint Milling	10	SY		\$ -	
9	332	<b>Full-Depth Reclamation</b>					
10	334	<b>Asphaltic Pavement</b>					\$ -
		Leveling Course SP9.5 (75 lbs/SY)	583.5	TON		\$ -	
		Resurface Lanes: SP12.5, C, PG76-22	1,283.7	TON		\$ -	
		New Lanes: SP12.5, C, PG76-22	570.5	TON		\$ -	
		Miscellaneous Asphalt: SP12.5, C, PG76-22	69.9	TON		\$ -	
		New Side Roads: SP12.5, C, PG76-22	45.9	TON		\$ -	
		New Dvwy Turnouts: SP12.5, C, PG76-22	8.1	TON		\$ -	
11	400	<b>Concrete Box Culvert - Concrete</b>					\$ -
		Class IV, 5.5 KSI Concrete (Includes Grade 60 Reinforcing Steel)	48.16	CY		\$ -	

## Bid Tabulation - Alternate Bid

County Road 127 North - Phase 2  
Road Segment 2  
Baker County, Florida

Bid By:

(company name)

Bid Item	FDOT Pay Item Group	Item Description	Qty.	Units	Item Unit Cost	Sub-Item Cost	Total Item Cost
12	430	<b>Storm Drainage - Pipe</b>					\$ -
		24" Round	24	LF		\$ -	
13	430	<b>Storm Drainage - End Sections</b>					\$ -
		Conc. Collar 24" (430.001)	6	EA		\$ -	
		FDOT HEADWALL (430-030) DBL 24"	4	EA		\$ -	
14	536	<b>Guardrail</b>					\$ -
		Guardrail - TL-3 (High Speed)	350	LF		\$ -	
		Special Steel Posts for Concrete Mount	4	EA		\$ -	
		End Treatment - Approach Terminal	4	EA		\$ -	
15	570	<b>Performance Turf</b>					\$ -
		Performance Turf (Seed)	18,153	SY		\$ -	
		Performance Turf (Sod)	7,780	SY		\$ -	
16	700	<b>Signage</b>					\$ -
		F&I Single Sign Post < 12SF	20	EA		\$ -	
		Mailboxes	7	EA		\$ -	
17	705	<b>Object Markers</b>					\$ -
		Object Markers, Type 2	12	EA		\$ -	
18	706	<b>Raised Pavement Markers</b>					\$ -
		Raised Pavement Markers	348	EA		\$ -	
19	710 & 711	<b>Traffic Markings</b>					\$ -
		White Solid 6" Paint	31,290	LF		\$ -	
		White Solid 24" Paint	37	LF		\$ -	
		Yellow 6" Skip (10'/30') Paint	14,082	LF		\$ -	
		Yellow 6" Solid Paint	13,871	LF		\$ -	
		White 24" Thermoplastic	37	LF		\$ -	
		White Message Thermoplastic	2	EA		\$ -	
20	000	<b>Construction Bond</b>	1	LS		\$ -	\$ -
Bidder has checked all calculations for accuracy prior to bid submittal.					<b>TOTAL BID =</b>		\$ -